

MATTHEWS & ASSOCIATES

Landscape Architecture & Construction

P.O. Box 3567 Vail, Colorado 81658



SPRINKLER ZONE OPERATING TIME

Project: ALNY

Date: 9-9-86

Job No.: _____

WATER REQUIRED for month of JULY with no rain:

MOWED LAWN = 1/2 in/week
 UN-MOWED LAWN = 3/4 in/week
 SHRUBS = 3/4 in/week
 GC & FLOWERS = 3/4 in/week

ZONE #	CLOCK STA.#	ZONE LOCATION	SPRINKLER HEAD	SPRINKLER NOZZLE	PRECIP. RATE	OPERATING TIME**	
						(@ <u>3 1/2</u> days/week)	
			RAINBIRD 1800	8-FLT 10-LA	1.8 in/hr	15 min	8
			TORO 570 OR RAINBIRD 1800	12'	1.5	20	10
			TORO 570 OR RAINBIRD 1800	15'	1.6	15	8
			TORO 300	01	.8	30	15
			TORO 300	02 03	.6	45	23
			TORO 300	63	.3	80	40
			TORO 300	93	.5	60	30
			TORO XP-300	#5	.5	50	25
			TORO XP-300	#7	.4	60	30
			RAINBIRD 15103	07	.2	150	75
			RAINBIRD 15103	09 LA	.2	120	60
			RAINBIRD 15111	5/32	.3	100	50

** = based on watering at night with no wind